



P.O. Box 2266  
Houma, LA 70361  
412 South Van Ave.  
Houma, LA 70363

985.868.1050  
866.357.1050  
985.868.5843 FAX

tbsmith.com


June 25, 2026

**ADDENDUM NO. 2**

**Terrebonne Parish Consolidated Government**

**LAKE CHIEN LIVING SHORELINE PROJECT**  
**PARISH PROJECT NO. 25-RAMP-19**

**TERREBONNE PARISH, LOUISIANA**  
**TBS Project No. 2025.0701**



**TO:** All holders of record of contract documents

**GENERAL:** The following items shall be considered part of the contract documents and shall be included in the same when the construction contract is executed. Changes made by addenda shall take precedence over original documents. Any changes which may affect construction or proper installation of materials or equipment not specifically mentioned in this addendum should be brought to the attention of the Engineer before submitting bid. Otherwise, such conditions, if found later to exist, must be worked out in an acceptable manner without additional cost to the Owner. General contractors are hereby advised to call attention of all subcontractors and/or suppliers to changes which may affect their work and/or product. Acknowledge receipt of this addendum by inserting its number, date of receipt, and signing or initialing in the proper blanks appearing of the Proposal Form. Failure to comply with the above may subject Bidder to disqualification and may be sufficient cause not to read or accept the bid.

This addendum consists of a total of **336** pages.

**I. BOOK OF CONTRACT DOCUMENTS & SPECIFICATIONS:**

**1. PART I, Book of Contract Documents & Specifications:**

A. Section, General Conditions, Article 5, Bonds and Insurance, Section 5.5, Information to Bidders, Paragraph 5.6, Minimum coverage, sub -paragraph 5.6.2.1, add the following at the end of sentence “, and with excess liability in the amount of \$4,000,000.00: (1) Manufacturer’s and Contractor’s Liability; (2) Contractual Liability; (3) Products Liability/Completed Operations; (4) Owners and Contractor’s Protective Liability-independent Contractors; (5) Personal Injury Liability.” Reference attached Encroachment Agreement for additional information for Genesis’s Encroachment insurance requirements.

**2. PART II, Plans:**

A. No changes or updates.

**3. PART III, Questions, Answers, and Clarifications**

A. **Question:** Looking to see if an alignment point table is available for the above referenced project in order to make a .kml file.

Answer: See attached KMZ and excel (.csv) file for requested information.

**B. Question:** Can you provide the coordinates for the revetments or a CAD drawing

Answer: See Question/Answer "A".

**C. Question:** Attached is Material Data Sheet from one of the aggregate suppliers. Please verify if this gradation meets the specifications for the project.

Answer: Yes, material data sheet for 4x1 Limestone meets the intent of the specifications.

**D. Question:** Project Access: The plans and permits in the specifications indicate an access route through oyster seed grounds and private oyster leases.

- a. In section SP 16.1, it states that the owner has acquired oyster lease areas impacted by the project. Does this include private oyster leases within the entire access route identified in the plans and specifications?
- b. In Section TS-110.4.2, it states that the owner has not secured access agreements through private oyster leases, and the contractor must obtain permission. Please clarify if access has been acquired by the owner.
- c. If the contractor remains in the permitted route, does this relieve the contractor from any oyster damage liability?
- d. Has an oyster assessment been performed for the access route?

Answer:

- a. See attached Oyster Lease Exhibit showing acquired oyster leases.
- b. See attached Oyster Lease Exhibit showing acquired oyster leases.
- c. Contractor to adhere to all permit requirements as stated in bid documents. Owner cannot guarantee relief of liability for oyster damage outside of acquired oyster leases.
- d. Yes, see attached TPCG Living Shoreline Lake Chien (TE-0177) Biological Oyster Assessment Report.

**E. Question:** Plan sheet 8 shows Revetment mattresses being placed over the 24" Genesis Pipeline, however there is no dredging within 50-ft of each side of the pipeline.

- a. Will the revetment mattresses be laid on top of the existing ground?
- b. If embankment is required in this area, where does the material come from? Is the expectation for the contractor to relay the material from the access/borrow canal?
- c. Can you provide a profile of the pipeline crossing showing the depth of cover, water depths, and natural marsh elevation?

Answer:

- a. No, revetment and required geotextile fabric to be placed on top of earthen fill as shown on plan sheet 14 of 24
- b. Refer to TS-300, Earthen Fill, Paragraph 300.4 in the project manual and notes on plan sheet 8 of 24. No dredging, excavation,

anchors, or spuds shall be permitted within fifty feet (50') of any existing pipeline.

c. See attached ASBUILT drawing for informational purposes only.

F. **Question:** Plan sheet 19 of 24, shows a Survey Transect labeled "CT6". This X-section is not provided in the plans. Can you provide this transect showing the pipeline depths?

**Answer:** Depth of cover of existing pipelines is not available at this time. Successful bidder will be required to provide this information as part of its pre-construction surveys. Reference Section TS-200. Also reference Specifications Appendix B, Magnetometer Survey, for additional information.

G. **Question:** I would also like to request the depth of cover for the 12" Gulf South Pipeline that we would be required to cross should Alternate 1 be awarded.

**Answer:** Depth of cover of existing 12" Gulf South Pipeline is not available at this time. Successful bidder will be required to provide this information as part of its pre-construction surveys. Reference Section TS-200, Surveying. Also reference Specifications Appendix B, Magnetometer Survey, for additional information.

H. **Question:** Will Freeze and Thaw testing be required as per 401.6.3.1?

**Answer:** Freeze and Thaw testing will not be required for this project.

\*\*\*\*\*

## II. ATTACHMENTS:

Slats Lucas Quarry Material Data Sheet for 4x1 Limestone (1 page)  
KMZ file (electronic file)  
Lake Chien Living Shoreline Coordinates (.csv) file (electronic file)  
Oyster Lease Exhibit (1 page)  
Poseidon Phase III ASBUILT Drawing dated April 14, 1998 (1 page)  
Encroachment Agreement (1 Page)  
Biological Oyster Assessment (330 pages)